

Regd. Office PSEB Head Office, The Mall Patiala-147001
Corporate Identity Number: U40109PB2010SGC033813 Website: www.pspcl.in
(Office of the Sr. XEN/Pilot Workshop, Sadiq Road, Sri Muktsar Sahib)
Email: asepmwks@gmail.com

To

NOTICE BOARD

Memo No.: 674/TE-03/PWMKS

Dated: 03/10/2022

Subject: - Press Tender Notice - Maintenance of Non-Residential Buildings (NRB) including Boundary wall and other maintenance civil works at Pilot Workshop Sri Muktsar Sahib during year 2022-23.

Tender Enquiry no- 03/ PWMKS/ 2022-23

Ref: - In continuation to this office memo no 590 dated: 26/08/2022.

Corrigendum-1

Last date of the subject cited tender enquiry is here by extended as under: -


Last date & time for sale of tender: -17/10/2022 Up to 05:00 PM

Last date & time for receipt of tender: -17/10/2022 Up to 05:00 PM

Last date & time for opening of tender: - 18/10/2022 at 3:00 PM

Other terms and conditions will be remains same as per original tender enquiry.


DA/ As above


Sr. Executive Engineer
Pilot Workshop, PSPCL,
Sri Muktsar Sahib.

Endst. No. 675/76 Dated 03/10/2022

Copy of the above is forwarded to following for information please: -

1. Chief Engineer, Civil Design & Construction, PSPCL, Patiala.
2. Dy CE/ CPW & MDI, PSPCL, Patiala.


Sr. Executive Engineer
Pilot Workshop, PSPCL,
Sri Muktsar Sahib.



PUNJAB STATE POWER CORPORATION LTD.

(Regd. Office PSEB Head Office, The Mall, Patiala)
Corporate Identification Number: U40109PB2010SGC033813 | Website: www.pspcl.in
(Contact number 96461-22952)

Tender Inquiry No. 03 /PWMKS/2022-23

Dated: 26.08.2022

Sr. Executive Engineer/Pilot Workshop, Sadiq Road, Sri Muktsar Sahib, invites press-tender for Maintenance of Non-Residential Buildings (NRB) including Boundary wall and other maintenance civil works at Pilot Workshop Sri Muktsar Sahib during year 2022-23. For detailed NIT & tender specification, please refer to <https://pspcl.in> from 29.08.2022 from 02:00 PM onwards.

Note: Corrigendum and addendum, if any, will be published online at <https://pspcl.in>



ਪੰਜਾਬ ਰਾਜ ਪਾਵਰ ਕਾਰਪੋਰੇਸ਼ਨ ਲਿਮਿਟਿਡ


(ਰਜਿਸਟਰਡ ਦਫਤਰ: ਪੀ.ਐਸ.ਈ.ਬੀ. ਮੁੱਖ ਦਫਤਰ, ਦੀ ਮਾਲ, ਪਟਿਆਲਾ)
ਕਾਰਪੋਰੇਟ ਪਛਾਣ ਨੰਬਰ: U40109PB2010SGC033813 | ਵੈੱਬਸਾਈਟ: www.pspcl.in
(ਸੰਪਰਕ ਨੰਬਰ 96461-22952)

ਟੈਂਡਰ ਇਨਕੁਆਰੀ ਨੰਬਰ: 03/ਪੀ. ਡਬਲਯੂ. ਐਮ .ਕੇ. ਐਸ /2022-23.

ਮਿਤੀ: 26.08.2022

ਸੀਨੀਅਰ ਕਾਰਜਕਾਰੀ ਇੰਜਿਨੀਅਰ / ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ, ਸਾਦਿਕ ਰੋਡ, ਸ਼੍ਰੀ ਮੁਕਤਸਰ ਸਾਹਿਬ ਵਲੋਂ ਸਾਲ 2022-23 ਵਿਚ ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ, ਸ਼੍ਰੀ ਮੁਕਤਸਰ ਸਾਹਿਬ ਵਿਖੇ ਗੈਰ-ਰਿਹਾਇਸ਼ੀ ਇਮਾਰਤਾਂ ਅਤੇ ਚਾਰ-ਦੀਵਾਰੀ ਦੀ ਸਾਂਭ-ਸੰਭਾਲ ਅਤੇ ਹੋਰ ਸਿਵਲ ਸਾਂਭ-ਸੰਭਾਲ ਦੇ ਕੰਮ ਲਈ ਪ੍ਰੈਸ-ਟੈਂਡਰ ਮੰਗੇ ਜਾਂਦੇ ਹਨ। ਐਨ. ਆਈ. ਟੀ. ਅਤੇ ਟੈਂਡਰ ਦੇ ਵੇਰਵੇ ਲਈ ਕਿਰਪਾ ਕਰਕੇ <https://pspcl.in> ਤੇ ਮਿਤੀ 29.08.2022 ਬਾਅਦ ਦੁਪਿਹਰ 02:00 ਵਜੇ ਤੋਂ ਦੇਖੇ ਜਾ ਸਕਦੇ ਹਨ।

ਨੋਟ: ਕੋਈ ਵੀ ਸੋਧ ਅਤੇ ਵਾਧਾ ਸਬੰਧੀ ਵੇਰਵੇ ਸਿਰਫ <https://pspcl.in> ਵੈਬਸਾਈਟ ਤੇ ਦੇਖੇ ਜਾ ਸਕਦੇ ਹਨ।


Senior Executive Engineer
Pilot Workshop, PSPCL
Sri Muktsar Sahib.

Regd. Office PSEB Head Office, The Mall Patiala-147001
 (Office of the Sr. XEN/Pilot Workshop, Sadiq Road, Sri Muktsar Sahib)

Email: asePWMKS@gmail.com

ਵੱਲ

NOTICE BOARD

ਮੀਮੋ ਨੰ:- 590 /TE 03/PWMKS ਮਿਤੀ:- 26 / 08 /2022.

ਵਿਸ਼ਾ: - ਪ੍ਰੈੱਸ ਟੈਂਡਰ ਨੋਟਿਸ - *Maintenance of Non-Residential Buildings (NRB) including Boundary wall and other maintenance civil works at Pilot Workshop Sri Muktsar Sahib during year 2022-23.*

Tender Enquiry no- 03 / PWMKS/ 2022-23

ਸ਼੍ਰੀ ਮਾਨ ਜੀ,

ਹੇਠ ਲਿਖੇ ਕੰਮ ਲਈ ਪੀ.ਐਸ.ਪੀ.ਐਲ ਦੀਆਂ ਨਿਯਮ ਅਤੇ ਸ਼ਰਤਾਂ ਅਨੁਸਾਰ ਮੋਹਰਬੰਦ ਟੈਂਡਰ ਮੰਗੇ ਗਏ ਹਨ ਜੋ ਕਿ ਮਿਤੀ 29 / 09 / 2022 ਨੂੰ ਸ਼ਾਮ 3:00 ਵਜੇ ਤੱਕ ਇਸ ਦਫਤਰ ਵਿਖੇ ਜਮ੍ਹਾਂ ਕਰਵਾਏ ਜਾ ਸਕਣਗੇ ਅਤੇ ਉਸੇ ਦਿਨ ਸ਼ਾਮ ਨੂੰ 3:30 ਵਜੇ ਖੋਲ੍ਹੇ ਜਾਣਗੇ। ਜੇਕਰ ਕਿਸੇ ਕਾਰਨ ਉਕਤ ਮਿਤੀ ਨੂੰ ਛੁੱਟੀ ਹੋ ਜਾਂਦੀ ਹੈ ਤਾਂ ਇਹ ਟੈਂਡਰ ਕੰਮ ਵਾਲੇ ਅਗਲੇ ਦਿਨ ਖੋਲ੍ਹੇ ਜਾਣਗੇ।

ਲੜੀ ਨੰ	ਕੰਮ ਦਾ ਸੰਖੇਪ ਵੇਰਵਾ	ਅਨੁਮਾਨਿਤ ਰਕਮ	ਬਿਆਨਾ ਰਕਮ	ਕੰਮ ਪੂਰਾ ਕਰਨ ਦੀ ਮਿਆਦ
1.	ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ, ਸ਼੍ਰੀ ਮੁਕਤਸਰ ਸਾਹਿਬ ਵਿਖੇ ਗੈਰ-ਰਹਾਇਸ਼ੀ ਇਮਾਰਤਾਂ ਅਤੇ ਚਾਰ-ਦਵਾਰੀ ਦੀ ਸਾਂਭ-ਸੰਭਾਲ ਅਤੇ ਹੋਰ ਸਿਵਲ ਸਾਂਭ-ਸੰਭਾਲ ਦੇ ਕੰਮ ਸਾਲ 2022-23. (ਵਿਸਥਾਰ ਪੂਰਕ ਵੇਰਵੇ ਲਈ Annexure-A ਦੇਖੋ)	3.53 ਲੱਖ	ਸਿਰਫ 7000/- ਰੁ:	6 ਮਹੀਨੇ

ਨਿਯਮ ਅਤੇ ਸ਼ਰਤਾਂ: -

- ਵਿਸਥਾਰ ਪੂਰਕ ਟੈਂਡਰ ਸਪੈਸੀਫਿਕੇਸ਼ਨ/ ਡਰਾਇੰਗ/ ਕੰਮ ਦਾ ਵੇਰਵਾ ਇਸ ਦਫਤਰ ਵਿੱਚ ਕੰਮ ਵਾਲੇ ਕਿਸੇ ਵੀ ਦਿਨ ਦੇਖੀ ਜਾ ਸਕਦੀ ਹੈ। ਸਿਰਫ ਉਹਨਾਂ ਠੇਕੇਦਾਰਾਂ ਦਾ ਟੈਂਡਰ ਸਵੀਕਾਰ ਕੀਤਾ ਜਾਵੇਗਾ ਜੋ ਰੁ: 590/- (ਸਮੇਤ GST) ਬਤੌਰ ਸਪੈਸੀਫਿਕੇਸ਼ਨ/ ਟੈਂਡਰ ਕੀਮਤ ਮਿਤੀ 28/ 09 /2022 ਨੂੰ ਸ਼ਾਮ ਦੇ 5:00 ਵਜੇ ਤੱਕ ਜਾਂ ਇਸ ਤੋਂ ਪਹਿਲਾਂ ਕਿਸੇ ਵੀ ਕੰਮ ਵਾਲੇ ਦਿਨ ਜਮ੍ਹਾਂ ਕਰਵਾ ਕੇ ਸਪੈਸੀਫਿਕੇਸ਼ਨ (ਟੈਂਡਰ ਡਾਕੂਮੈਂਟ) ਜਾਰੀ ਕਰਵਾਉਣ ਲਈ ਬਿਨੈ-ਪੱਤਰ ਦੇਣਗੇ। ਟੈਂਡਰ ਮਿਤੀ 28 / 09 /2022 ਨੂੰ ਸ਼ਾਮ ਦੇ 5:00 ਵਜੇ ਤੱਕ ਜਾਰੀ ਕੀਤੇ ਜਾਣਗੇ ਅਤੇ ਉਹ ਹੇਠ ਲਿਖੀਆਂ ਸ਼ਰਤਾਂ ਪੂਰੀਆਂ ਕਰਦੇ ਹੋਣ :-
 - ਠੇਕੇਦਾਰ, ਕੰਪਨੀ ਜਾਂ L&C society ਦਿ PWD (B&R)/ PSPCL/ PSTCL/ NTPC/ State Electricity Utilities ਅਧਿਕਾਰੀਆਂ ਵਿਚ ਸਿਵਲ ਦੇ ਕੰਮ ਕਰਨ ਲਈ ਨਾਮਜ਼ਦਗੀ ਹੋਣੀ ਲਾਜ਼ਮੀ ਹੈ।
 - ਟੈਂਡਰ ਭਰਣ ਵਾਲੇ ਦਾ EPF commissioner ਕੋਲ ਰਜਿਸਟਰ ਹੋਣਾ ਅਤੇ EPF Code ਨੰਬਰ ਹੋਣਾ ਲਾਜ਼ਮੀ ਹੈ।
 - ਟੈਂਡਰ ਭਰਣ ਵਾਲੇ ਕੋਲ PAN, EPF, GST No & ESI No. ਹੋਣਾ ਲਾਜ਼ਮੀ ਹੈ।

Note: As per Punjab Govt. notification no.: 76/52/78-C.1(5)/43/42 dated 02-10-2014 issued by Registrar Co-op Societies, Punjab; preference will be given to Co-op Societies for participation in this tender for work of skilled nature and contract value below 40 lakhs. The tenders of the contractors will be considered only in case minimum 03 number tenders are not received from Co-op Societies.

2. ਬਿਆਨਾ ਰਕਮ (if applicable) ਸੀਨੀਅਰ ਕਾਰਜਕਾਰੀ ਇੰਜੀਨੀਅਰ, ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ, ਸ਼੍ਰੀ ਮੁਕਤਸਰ ਸਾਹਿਬ ਦੇ ਦਫਤਰ ਵਿਚ ਨਕਦ ਜਮਾਂ ਕਰਵਾਈ ਜਾਵੇ ਜਾਂ ਉਸ ਦੇ ਹੱਕ ਵਿੱਚ ਡਿਮਾਂਡ ਡਰਾਫਟ ਜੋ ਕਿ ਸ਼੍ਰੀ ਮੁਕਤਸਰ ਸਾਹਿਬ ਵਿੱਚ ਭੁਗਤਾਨ ਯੋਗ ਹੋਵੇ ਨਾਲ ਨੱਥੀ ਕੀਤਾ ਜਾਵੇ।
3. ਸ਼ਰਤਾਂ ਵਾਲਾ ਟੈਂਡਰ ਜਾਂ ਤਾਰ/ ਫੈਕਸ ਰਾਹੀਂ ਮੰਗੇ ਗਏ ਟੈਂਡਰ ਸਵੀਕਾਰ ਨਹੀਂ ਕੀਤਾ ਜਾਵੇਗਾ।
4. ਸਮਰਥ ਅਧਿਕਾਰੀ ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ ਸ਼੍ਰੀ ਮੁਕਤਸਰ ਸਾਹਿਬ ਜੀ ਨੂੰ ਕਿਸੇ ਵੀ ਟੈਂਡਰ ਦੇ ਜਾਂ ਸਾਰਿਆਂ ਟੈਂਡਰਾਂ ਨੂੰ ਬਿਨਾਂ ਕੋਈ ਕਾਰਨ ਦੱਸੇ ਰੱਦ ਕਰਨ ਦਾ ਹੱਕ ਹੋਵੇਗਾ।
5. ਟੈਂਡਰ ਖੋਲਣ ਦੀ ਮਿਤੀ ਤੱਕ ਸੀ.ਐਸ.ਆਰ ਦੇ ਸਬੰਧ ਵਿੱਚ ਜਾਰੀ ਕੀਤੀਆਂ ਸਾਰੀਆਂ ਸੋਧਾਂ ਜਿਸ ਵਿਚ ਏ ਅਤੇ ਸੀ ਸਲਿੱਪ ਵਜੋਂ ਸ਼ਾਮਲ ਹਨ, ਲਾਗੂ ਹੋਣਗੀਆਂ।
6. ਠੇਕੇਦਾਰ ਨੂੰ ਈ.ਐਸ.ਆਈ ਐਕਟ ਅਤੇ ਈ.ਪੀ.ਐਫ ਅਤੇ ਲੇਬਰ ਐਕਟ ਦੀਆਂ ਧਾਰਾਵਾਂ ਨੂੰ ਮੰਨਣਾ ਪਵੇਗਾ ਅਤੇ ਇਹਨਾਂ ਐਕਟਾਂ ਅਧੀਨ ਹੋਣ ਵਾਲੀਆਂ ਅਦਾਇਗੀਆਂ ਕਰਨੀਆਂ ਪੈਣਗੀਆਂ।
7. ਟੈਂਡਰ ਖੋਲਣ ਦੀ ਮਿਤੀ ਤੋਂ 120 ਦਿਨ ਤੱਕ ਭਰੇ ਗਏ (Quoted) ਰੇਟ ਲਾਗੂ ਰਹਿਣਗੇ।
8. ਬਿਲ ਸਹਾਇਕ ਇੰਜੀਨੀਅਰ ਦੇ ਦਫਤਰ ਵਿੱਚ ਤੁਹਾਡੇ ਵੱਲੋਂ ਪੇਸ਼ ਕਰਨਾ ਹੋਵੇਗਾ। ਇਸ ਦੀ ਅਦਾਇਗੀ ਮੰਡਲ ਲੇਖਾ ਸੁਪਰਡੰਟ ਵੱਲੋਂ ਚੈਕ ਕਰਨ ਉਪਰੰਤ ਹੀ ਕੀਤੀ ਜਾਵੇਗੀ।
9. ਠੇਕੇਦਾਰ ਵੱਲੋਂ ਆਪਣੀ ਲੇਬਰ ਨੂੰ ਪੇਮੈਂਟ ਪੰਜਾਬ ਲੇਬਰ ਰੇਟਾਂ ਤੇ ਕਰਨੀ ਹੋਵੇਗੀ।
10. ਠੇਕੇਦਾਰ ਨੂੰ GST ਦੀ ਅਦਾਇਗੀ ਉਸ ਵੱਲੋਂ ਜਮ੍ਹਾਂ ਕੀਤੀ ਰਕਮ ਦੇ ਦਸਤਾਵੇਜ਼ ਪੇਸ਼ ਕਰਨ ਉਪਰੰਤ ਕੀਤੀ ਜਾਵੇਗੀ।
11. ਕੰਮ ਸਮੇਂ ਸਿਰ ਨਾ ਕਰਨ ਦੀ ਸੂਰਤ ਵਿਚ $1\frac{1}{2}\%$ ਅਲਾਟਿਡ ਲਾਗਤ ਦਾ ਪ੍ਰਤੀ ਹਫਤਾ ਜਾਂ ਉਸ ਦੇ ਹਿੱਸੇ ਵਜੋਂ ਬਾਕੀ ਰਹਿੰਦੇ ਕੰਮ ਦਾ ਜੁਰਮਾਨਾ ਵਜੋਂ ਵਸੂਲ ਕੀਤਾ ਜਾਵੇਗਾ। (ਜੁਰਮਾਨੇ ਦੀ ਸਮੁੱਚੀ ਕੀਮਤ ਅਲਾਟਮੈਂਟ ਆਰਡਰ ਵਿਚ ਦਰਸਾਈ ਕੁਲ ਰਕਮ ਦਾ 10% ਤੋਂ ਵੱਧ ਨਹੀਂ ਹੋਵੇਗਾ)। ਵਰਕਸ਼ ਰੈਗੂਲੇਸ਼ਨ 1997 ਦੀ ਧਾਰਾ 3.14 ਅਨੁਸਾਰ ਲਾਗੂ ਹੋਵੇਗਾ।
12. ਕੰਮ ਦੌਰਾਨ ਉਸਾਰੀ ਲਈ ਪੀ.ਐਸ.ਪੀ.ਐਲ ਵੱਲੋਂ ਜਾਰੀ ਸੀਮਿੰਟ ਹੀ ਵਰਤਣਾ ਲਾਜ਼ਮੀ ਹੋਵੇਗਾ।

ਸੀਨੀਅਰ ਕਾ: ਕਾ: ਇੰਜੀਨੀਅਰ
ਪਾਇਲਟ ਵਰਕਸ਼ਾਪ ਸ਼੍ਰੀ ਮੁਕਤਸਰ ਸਾਹਿਬ

ANNEXURE-A


Detail of work items to be executed against TE- 03 /PWMK/2022-23

SN	CSR Ref	Narration	Unit	Qty
1	8.5 (b)	Dismantling brick work tile masonry or tile lining - in cement	cum	27.738
2	8.6 (d)	Dismantling concrete - 1:2:4 mix	cum	2.000
3	8.16	Dismantling cement conglomerate floors 25mm to 50mm thick including concrete base.	sqm	6.335
4	8.26 (b)	Removing Doors and Windows (Steel or wood) with chowkhats by making recesses in walls when the wall is not to be dismantled.-- Windows of area 3 sqm and below	each	2.000
5	8.31 (c)	Scraping cement plaster	sqm	44.034
6	8.31 (e)	Scraping Bricks dismanteled from brick work in lime or cement	Nos	5,326.000
7	8.36	Dismantling asbestos cement, celotax or other hard board ceiling or partition walls including supporting timber.	sqm	28.000
8	AOR-3	Cement Concrete 1:2:4 with stone ballast or shingle mixing by mechanical means using concrete mixer volumetric type (without water charges @3% of labour cost) [CSR Ref- 10.13 a (ii)]	cum	2.000
9	AOR-4	Reinforced cement concrete M-20 mechanically batch mixed using volumetric type concrete mixer as per IS:1791 and vibrated by needle vibrator but excluding steel reinforcement centering and shuttering in foundation and plinth (without water charges @3% of labour cost) [CSR Ref- 10.15]	cum	0.709
10	13.19	Corrugated asbestos Sheet roofing 6 mm thick sheets fixed with GI hooks and bolts, limpet and bitumen washers complete fixed in position excluding the cost of perlins, rafters and trusses	sqm	28.000
11	AOR-5	First class burnt brick work laid in cement sand mortar 1:4 in foundation and plinth. (without water charges @3% of labour cost) [CSR Ref- 11.7]	cum	1.035
12	AOR-6	First class burnt brick work laid in cement sand mortar 1:5 in foundation and plinth. (without water charges @3% of labour cost) [CSR Ref- 11.5]	cum	20.286
13	AOR-7	First class burnt brick work laid in cement sand mortar 1:5 in first storey upto 4 metres above plinth level. [CSR Ref- 11.6]	cum	7.452
14	14.72	Providing and laying Anti skid Ceramic floor tiles of size 300x300 mm x 10 mm thick of 1st quality conforming to IS :15622 of approved make in colours such as White, Ivory, Grey, Fume Red Brown, laid on flooring skirting and dado in 12.5mm thick cement plaster 1 :3 in base and jointed with @ 3.3 kg/sqm including pointing the joints with white cement and matching pigment etc., completewhite cement slurry in joints including corners angles and beading.	sqm	6.335
15	14.12 5	Providing and fixing 1st quality ceramic glazed wall tiles MatUSemi MatUGlosy/Highly Gloss finish/ Highlighter/ emboss conforming to IS 15622	sqm	27.034

		(thickness to be specified by the manufacture of approved make in all colours, shades except burgundy, bottle green, black of size 200 x 300 mm, 100x200mm, 200x200mm as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1 :4 (1 cement: 4 fine sand) and jointing with grey cement slurry @ 3.3kg per sqm including pointing in white cement mixed with pigment of matching shade complete.		
16	AOR-8	12.5mm thick cement plaster 1:4 [CSR Ref- 15.09]	sqm	40.500
17	AOR-9	12.5mm thick cement plaster 1:5 [CSR Ref- 15.10]	sqm	81.600
18	AOR-10	20mm thick cement plaster 1:5 in two coat work [CSR Ref- 15.21]	sqm	92.640
19	16.1	White washing (First coat or subsequent one coat)	sqm	300.740
20	16.8	Distempering with dry distemper of approved manufacture one coat on old distempered work.	sqm	59.440
21	16.14	Finishing walls with exterior decorative cement based paint such as snowcem, robbiacem etc. two coats to give an even shade.	sqm	182.800
22	16.19	Painting two coats with synthetic enamel paints in all shades on old wood work or metallic or plastered or concrete surface to give an even shade including rubbing down old paint.	sqm	110.740
23	17.23 (ii)	Cost of Aluminium fittings complete for doors, windows such as tower bolts, handles, Stoppers and screw etc. for these fittings (Excluding sliding bolt) -- For shutter area above 0.50 sqm	sqm	4.084
24	17.45 (a)	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate z sections and other sections conforming to Is: 733 and IS :1285 of Jindal, Hindalco, Mahavir or equivalent make approved by Engineer in Charge , fixed with rawl plugs and screws or with fixing clips, or with expansion hold fasteners including necessary filling up of gaps at junctions, at top, bottom and sides with required PVC Plug/neoprene felt etc. Aluminium sections shall be smooth, rust free, straight, mitered and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing/paneling, C.P.brass/stainless steelscrews, all complete as per architectural drawings and the directions of Engineer-InCharge. (Glazing and paneling to be paid for separately) : -- For fixed portion and chaukhats	kg	35.465
25	17.45 (b)	For shutters of doors, windows & ventilators including providing and fixing hinges/pivots and labour for fixing of fittings wherever required including the cost of PVC Plug / neoprene gasket required.	kg	25.351
26	17.47 (i)	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with PVC Plug/ neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item) -- Float glass panes of 5 mm	sqm	2.758

N

		thickness		
27	17.96	Providing and fixing aluminium Wire Mesh including cost of necessary fittings i.e. screws,u-type Beeding etc. complete	kg	3.000
28	18.18	Cold twisted deformed (Ribbed/ Tor Steel Bar) Bars Fe 500 grade as per IS 1786-2008, for R.C.C works, where not including in the complete rate of RCC including binding & bending and placing in position complete	Qtl	0.603
29	28.20 (b)	INTERNAL - EXPOSED ON WALL: Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes as per IS15778 (ISI marked with the prior approval of Engineer-in-charge), having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings including fixing the pipe with clamps at 1.00 m spacing including jointing of pipes & fittings with one step PVC solvent cement and testing of pipes complete as per direction of Engineer-in-Charge. -- SDR 11 CPVC pipes & fittings 20mm o/d	mtr	6.000
30	28.35 (a)	Providing, laying, jointing, fixing and testing ISI Marked G.I. Pipe (as per IS-1239) B-Class including cost of specials (such as tees, bends, sockets, elbows etc.), painting with anti-corrosive bitumastic paint, testing, cutting, threading Inside building complete.-- 15mm i/d	mtr	6.000
31	30.47 (d)	Providing and fixing in position stainless steel sinks of approved make (to the approval of Engineer-in-charge) 1mm thick,grade-304 (18/8) with waste coupling complete in all respect. -- Double bowl Sink without drain board Overall size 1114 x 490mm with bowl size 460x385x200mm including waste coupling	No	1.000
32	30.48	Providing & fixing in postion C.P. brass Sink Cock with swinging spout (wall mounted) of approved make (to the approval of Engineerin-charge) complete in all respect.	No	1.000
33	NS	Cleaning of spetic tank including taking out and dumping of grit at appropriate site as per instructions of Engineer-in-charge. (Lumsum rate)	job	1.000


Sr. Executive Engineer
Pilot Workshop, PSPCL
Sri Muktsar Sahib